


राजेन्द्र शिशु सदन
डा० राजेन्द्र प्रसाद केन्द्रीय कृषि विश्वविद्यालय पूसा, समस्तीपुर

पत्रांक: 147 रा०शि०स०, पूसा

दिनांक 19:04.2025

कोटेशन सूचना

सर्वसाधारण को सूचित किया जाता है कि राजेन्द्र शिशु सदन, पूसा में ईबी संख्या-11 के जीर्णोद्धार एवं आधारभूत संरचना विकास हेतु कोटेशन आमंत्रित किया जा रहा है। इच्छुक एजेंसी/फर्म जो राष्ट्रीय ख्याति के केन्द्रीय/पीएसयू/राज्य सरकार विभाग में कार्यरत है, अपना आवेदन बंद लिफाफे में सूचना निर्गत की तिथि के 10 दिनों के अन्दर (30-4-2025, बुधवार 1 PM तक) प्राचार्य, राजेन्द्र शिशु सदन, पूसा के कार्यालय कक्ष में भारतीय डाक सेवा (स्पीड पोस्ट) से पहुँच जाना चाहिए।


19/4/2025
सचिव

राजेन्द्र शिशु सदन

Dr. Sudhanand P. Lal
Asst. Prof. cum Scientist
PG Dept. of Extension Education
F. CAU, Pusa, Samastipur-848125

नोट: कृपया 4 पेज संलग्नक देखें

Notice Inviting Quotation

Sishu Sadan School Dr. Rajendra Prasad Central Agricultural University Pusa invites item wise rate quotation for given under single bid from the experienced and financially as well as technically sound agencies working in central / PSU / state government departments of national repute for Painting of Sishu Sadan School (Inner & Outer) at EB No.11 DRPCAU, Pusa and Provision of shed in front and courtyard of Sishu Sadan School (EB No -11) , under DRPCAU Pusa Samastipur Bihar .

Detail specification of work as follows:

Quotation for Painting of Sishu Sadan School (Inner & Outer) at EB No.11 ,DRPCAU,Pusa				
Item No.	Description of Item	Qty.	Unit	Rate quoted by Agency (in figures and Words)
1	12 mm cement plaster of mix :1:6 (1 cement: 6 fine sand)	50.00	Sqm	
2	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand)	20.00	Sqm	
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.Two coats	1743.02	Sqm	
4	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	695.34	Sqm	
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	400.55	Sqm	

6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	43.26	Sqm	
7	Cost repairing windows / ventilators and painting in same pattern and design etc all complete job as per specification and direction of E/I.	6.00	Job	
8	S/F/F MS Doors / window chajja made of angles with corrugated sheet as per requirement all complete job as per specification and direction of E/I.	2.000	Job	
			Total	

Quotation for Provision of shed in front and courtyard of Sishu Sadan School (EB No -11) , DRPCAU Pusa

Item No.	Description of Item	Qty.	Unit	Rate quoted by Agency (in figures and Words)
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.81	cum	
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	1.22	cum	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	2.80	cum	
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.Hot finished welded type tubes	1982.00	kg	
5	S/F/F color coated roof sheet with minimum thickness 0.45 mm (TATA Durashine / kamdhenu / Jindal make) including J & L hook all complete job as per specification and direction of E/I.	409.00	sqm	

6	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	50.00	sqm	
7	Supplying and filling in plinth with Local sand under floors, including watering, ramming, consolidating and dressing complete.	9.18	cum	
8	Providing 100A one brick flat soling joint filled with sand all complete as per specification and direction of E/I.	15.300	sqm	
9	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate with sand all complete as per specification and direction of E/I.	256.860	sqm	
				Total